

Standard Truck Kitchen Construction & Pricing Information

Major Kitchen Systems

Electrical

- All Electrical is installed by a certified electrician and upon completion is inspected by **Intertek** and tested to SPE 1000

Propane

- Permits are pulled for equipment
- Piping is run and tested by a certified gas fitter
- Propane is tested to CSA B149.1-10
- Once equipment is installed, a secondary inspection is performed and the mobile food unit is inspected and a permit is received from **Technical Safety B.C.**

Fire Suppression

- If required, is installed by certified installer **Great West Fire & Safety Ltd.**

All Pricing is exclusive of applicable taxes

Kitchen Interior Build - \$1365 per lineal foot

Strip Van of Unwanted Shelving & Cabinets (If required and subject to evaluation of all items needing to be removed)

Rough Lay Out of Equipment & Counters to determine location for all cut outs

Cut Outs Framed and Structure Welded into Place

Electrical / Outlets / Panel / Switches / Wiring - Install

30 Amp 120/240 Generator Electrical Panel (Upgrade to 60 Amp if Required)

Electrical Outlets as Required

Electrical Inspection by Intertek / Approval Label attached

Walls , Ceilings, Spray Foam Insulation, 1" Roxul High Heat Insulation on Cook Area Wall

Ceiling Skinned w white powder coated alum sheet

Walls Skinned w 304 #4 quilted stainless

2- 3 Custom roof vents with gas springs and interior locking latches (pending roof size)

Large Service Window Fabricated from aluminum complete with gas springs & interior locking latches

1/8 Aluminum checker plated flooring , all edges and seams are sealed to prevent moisture from getting under floor

Install of Sealed Fluorescent Lighting as required

Two Exterior Marine Grade Speakers

Two Exterior Spot Lights mounted on both sides of Service Window

Fabricating & Install Rear Bulkhead - \$3500

If required, includes frame and fabricated man door

Plexi-Glass Inserts for Service Window and Bug Screens for Vents - \$1800

Custom Equipment & Preparation Counters w Cabinet Doors & Latches - \$375 per foot

Interior & Exterior Stainless Shelving - \$150 per foot

Water System - \$6195

Stainless 3 Compartment Sink Custom Mounted Into Countertop w Hot & Cold Faucet
Stainless Hand Wash Sink
30 Imp Gallon / 136 Litres Fresh Water Tank
40 Imp Gallon / 182 Litres Waste Water Tank
6 Gallon Propane Fired Suburban Water Heater
Shurflo 3.0 GPM Delivery Water Pump
Stainless Tube Cabinet w Cabinet Doors
Water Fill & City Water Fill
Waste Water Drain Hose
Hand Soap & Towel Dispenser

Gas System - \$5900

Permit Pulled for Propane System
High Rating BTU regulator
Shut-off Valves at all Appliances
Black Iron Piping to all Appliances
Mounted Bottle Racks on Rear of Trailer
120 V Interlock Solenoid & 120 V Interruption Switch
Propane Detector

System is inspected and approved by Technical Safety BC

Generator Compartment - \$3200

Hole Cut Out for Generator Compartment
Custom Generator Tray Framing with Steel Angle Tubing
Flip up Door with locking latches
Steel & Aluminum Angle Generator Tray with Heavy Duty Sliders

Generator Install - \$1250

Mounting, Wiring to Panel Box and Fuel Hook Up

Exhaust Hood 4-6FT - \$5200

Custom Stainless 4-6FT Steel Hood & Shroud w Commercial Exhaust Fan
Stainless Steel Grease Filters & Drip Trays
Extra \$400 per foot on hoods over 6 FT

Equipment Installation \$1-\$3000

Includes forklift Off Loading from Carrier, Uncrating, Modifications & Assembly (if required), Custom Cabinets & Approved Hoses, Testing, Kick Plating

Truck Kitchen Options:

Fryer Splash Guards & Lids - \$350

Triple Sink Covers -